

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 6-2-53 (of this well) 6/86  
*completed on*

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil & Gas Corporation OPERATORS LICENSE NO. 5447

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Brand "A" WELL NO. 1 WELL LOCATION SE SE NE COUNTY Kingman

SEC. 16 TWP. 29 RGE. 7 ~~(S)~~ or (W) TOTAL DEPTH 4515 PLUG BACK TD 3830

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_  
Conductor 13" 90 125  
SURFACE CASING SIZE 8-5/8" SET AT 278 CEMENTED WITH 200 SACKS  
CASING SIZE 5-1/2" SET AT 4512 CEMENTED WITH 250 SACKS  
PERFORATED AT 3727-37 & 3763-73 LKC

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_

See Attachment

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? completed on 6-2-53  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN June 12, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 6-4-86

Earl Rollings - Production Foreman PHONE # (316) 672-9388

ADDRESS Box 381, Pratt, Kansas 67124

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. \_\_\_\_\_

ADDRESS Box 347, Chase, Kansas 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hui  
(Operator for Agent)

DATE: 6/2/86

2

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 04 1986  
CONSERVATION DIVISION  
Wichita Kansas

BRAND "A" #1

PLUGGING PROCEDURE

1. Plug back using sand to 3700'. Place 5 sacks cement above.
2. Shoot off 5-1/2" Production Casing and recover same.
3. Pump down 8-5/8" surface casing as follows; 3 sacks hulls, 15 sacks gel, and 65-75 sacks Halliburton "Light" or equivalent. A wiper plug must be used if so warranted.

Verbal approval given by Warren Kirkpatrick of Wichita District Office. 3/21/86

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 04 1986  
CONSERVATION DIVISION  
Wichita, Kansas



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

SEP 4 1986

June 4, 1986

EXPIRES

WELL PLUGGING NOTICE

Brand "A" #1  
SE SE NE  
Sec. 16-29S-7W  
Kingman County

Cities Service Oil & Gas Corporation  
3545 N.W. 58th Street  
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

*William R. Bryson*

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #2 3244 E. Douglas Wichita, KS 67208 316-651-5506

five days prior to plugging the well (KAR-82-3-113).