

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-20415-0000 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Texaco Inc. OPERATORS LICENSE NO. 5153
ADDRESS Box 2420 Tulsa, Oklahoma 74102 PHONE # (918) 560-6333
LEASE (FARM) Cord Wells Unit WELL NO. 2 WELL LOCATION C NE NW COUNTY Kingfisher
SEC. 27 TWP. 29S RGE. 8W (S) or (W) TOTAL DEPTH 4279 PLUG BACK TD 4232

Check One:

OIL WELL _____ GAS WELL D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 256 CEMENTED WITH 200 SACKS.
CASING SIZE 5 1/2 SET AT 4199 CEMENTED WITH 90 SACKS
PERFORATED AT 4163-4202

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 25 sks. of cement to plug perfs.
pump to 4100' Shoot 5 1/2 & pull to 300'. Pump 50 sks. of cement @ 300 to 200
Lay down 5 1/2 and put 10 sks. of cement @ 40 to 0 Cut off & cap
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS Robert Sargent PHONE # (316) 624-7455

ADDRESS 620 S. Lincoln Liberal, Kansas 67901 RECEIVED
STATE CORPORATION COMMISSION
624-7455
APR - 4 1988

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS Box 506 Liberal, Kansas 67905-0506 PHONE # (316) 624-7455
CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert Sargent
(Operator or Agent)

DATE: 3-31-88

2

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

CORD WELLS #2
 NE-NW Sec 27-29S-8W
 Kingman County Kansas


Commenced: 11-11-75

Completed: 11-22-75

OPERATOR: Texaco, Inc.

Depth		Formation	Remarks
From	To		
0	50	Redbed	Ran 6 jts of 8 5/8" csg set @ 258' Cemented w/ 250 sks Posmix 3% CC PD @ 8:30 p.m. 11-11-75
50	258	Redbed-Shells	
258	1050	Redbed-Shale	
1050	1450	Shale-Shells	
1450	1620	Shale-Lime	
1620	1805	Lime	
1805	1945	Lime-Shale	
1945	2630	Shale-Lime	
2630	2855	Lime	
2855	3115	Shale-Sand	
3115	3325	Lime-Shale	Ran 100 jts of New 5 1/2" csg set @ 4278" Cemented w/200 sks Posmix 18% Salt 3/4 of 1% Gilsonite per sack P. D. @ 8:45 p.m. 11-22-75
3325	3530	Lime-Shale-Sand	
3530	4278	Lime	
4278 - TD			

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled NE-NW Sec 27-29S-8W, Kingman County Kansas to the best of my knowledge and belief.


 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 4th day of December, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official the day and year last above written.

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

April 7, 1988

APR 7 '88

WELL PLUGGING NOTICE

EXPIRES

Cord Wells Unit #2
C NE NW
Sec. 27-29S-08W
Kingman County

Texaco, Inc.
Box 2420
Tulsa, OK 74102

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist in cursive.

Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809