

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-20016-0001 (of this well) C/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Texaco Inc. OPERATORS LICENSE NO. 5153

ADDRESS Box 2420 Tulsa, Oklahoma 74102 PHONE # (918) 560-6333

LEASE (FARM) Cord Well Unit WELL NO. 1 WELL LOCATION C NW NE COUNTY Kingfisher man

SEC. 27 TWP. 29S RGE. 8W or (W) TOTAL DEPTH 4219 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 256 CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2 SET AT 4199 CEMENTED WITH 90 SACKS

PERFORATED AT 4188-4192 4192-4199 O.H. 4199-4219

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 25 sks. of cement w/top @ 4100'

Shoot & pull 5 1/2 to 300' Pump 50 sks. of cement @ 300 to 200 Pull 5 1/2 & put 10 sks.

of cement @ 40 to 0 Cut off & cap

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Robert Sargent PHONE # (316) 624-7455

ADDRESS 620 S. Lincoln Liberal, Kansas 67901

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 CONSERVATION DIVISION Wichita, Kansas 6/88

ADDRESS Box 506 Liberal, Kansas 67905-0506 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert Sargent
(Operator or Agent)

DATE: 3-31-88

②

RECEIVED
STATE CORPORATION COMMISSION

APR - 4 1988

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

CORD WELLS UNIT #1
C NW NE SECTION-27-29S-8W
KINGMAN COUNTY, KANSAS

COMMENCED: MARCH 23, 1967
COMPLETED: APRIL 2, 1967

OPERATOR - Texaco Inc.

DEPTH		FORMATION	REMARKS
FROM	To		
0	257	RED BED AND SHALE	RAN 7 JOINTS OF 8-5/8" CASING SET @ 256' w/200 SACKS CEMENT.
257	920	RED BED AND SHALE	
920	1300	SHALE	
1300	1435	SHALE AND LIME	
1435	2000	LIME	
2000	2990	SHALE AND LIME	
2990	4060	LIME	
4060	4178	LIME AND SHALE	
4178	4200	LIME	
4200	TD		RAN 129 JOINTS OF 5 1/2" CASING SET @ 4199' w/100 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NW NE SECTION 27-29S-8W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.



E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 5TH DAY OF APRIL, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.


BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

JUL 7 '88

EXPIRES

April 7, 1988

WELL PLUGGING NOTICE

Cord Well Unit #1
C NW NE
Sec. 27-29S-08W
Kingman County

Texaco, Inc.
Box 2420
Tulsa, OK 74102


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809