

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO; injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Petroleum Inc. API NO. 15-175-20556-0000  
 ADDRESS P. O. Box 1255 COUNTY Seward  
Liberal, KS 67901 FIELD Wildcat ARKALON  
 \*\*CONTACT PERSON Merle Evers LEASE Irwin  
 PHONE 316-624-1686

PURCHASER NA WELL NO. 2  
 ADDRESS \_\_\_\_\_ WELL LOCATION NE SW NW/4  
 \_\_\_\_\_ 1660 Ft. from North Line and  
 \_\_\_\_\_ 880 Ft. from West Line of  
 the SEC. 34 TWP. 32S RGE. 32W

DRILLING CONTRACTOR Zenith Drilling  
 ADDRESS 505 Fourth Financial Center  
Wichita, Kansas 67202

PLUGGING CONTRACTOR Dowell  
 ADDRESS Ulysses, Kansas

TOTAL DEPTH 6110' PBTD \_\_\_\_\_  
 SPUD DATE 10/10/81 DATE COMPLETED 10/22/81  
 ELEV: GR 2810 DF 2818 KB 2820



WELL PLAT  
 (Quarter) or Full Section - Please indicate.

KCC ✓  
 KGS ✓  
 MISC. ✓

DRILLED WITH (~~DRUM~~) (ROTARY) (~~WDR~~) TOOLS  
 Report of all strings set — surface, intermediate, production, etc. (New)/(~~USED~~) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 7/8	8 5/8	24#	1626	Liteweight Class "H"	700 200	3/4# floeal, 2%cc 3%cc

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD	
Size	Setting depth

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil <u>RECEIVED</u> bbls.	Gas <u>MCF</u>	Water <u>W</u> bbls.
Disposition of gas (vented, used for heating, etc.)	Producing interval (s)		Gas-oil ratio <u>CFPB</u>

11-12-81

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unknown Depth 550  
 Estimated height of cement behind pipe surface

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4270-4300 30"-60"-60"-120"			Winfield	2736
IHP - 2035 FHP - 2003			Council Grove	2952
IHP - 81-212 FFP - 245-326			Heebner	4243
ISI - 882 FSI - 898			Toronto	4282
REC. 120' muddy salt water slightly gas cut; 540' slightly gas cut salt water			Lansing	4370
			Marmaton	5008
			Cherokee	5190
			Morrow	5513
			Chester	5637
			St. Gen.	5834
			St. Louis	5929
DST #2 4369-4383 30"-60"-60"-120"				
IHP - 2141 FHP - 2093				
IHP - 32-48 FFP - 80-112				
ISI - 1273 FSI - 1257				
REC. 60' watery mud; 120' salt water				
DST #3 5928-5940 30"-60"-60"-120"				
IHP - 2867 FHP - 2835				
IHP - 64-80 FFP - 96-129				
ISI - 1803 FSI - 1819				
REC. 150' oily drlg. mud; 30' watery oily mud; 60' salt water				
DST #4 5568-5640 Misrun				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**A F F I D A V I T**

STATE OF Kansas, COUNTY OF Seward SS,

Merle Evers OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Dist. Superintendent FOR Petroleum Inc. OPERATOR OF THE Irwin LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 24 DAY OF October 1981, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Merle Evers

SUBSCRIBED AND SWORN TO BEFORE ME THIS 11th DAY OF November 1981

STATE NOTARY PUBLIC  
 JAMES R. HATFIELD  
 Seward County, Kansas  
 My Appt. Exp. 9/25/82

James R. Hatfield  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: