

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 - 175 - 20505-00-00
County Number

Operator Rincon Operating Co.
Address 1580 Lincoln Street Suite 700, Denver CO 80295

Well No. 1 Lease Name Parsons Jones

Footage Location 660 feet from (N) ~~XXX~~ line 1980 feet from (E) ~~XXX~~ line


Principal Contractor J. W. Gibson Geologist Don L. Huber

Spud Date 12/16/80 Date Completed 2/4/81 Total Depth 6350' P.B.T.D. 6234'

Directional Deviation Oil and/or Gas Purchaser Northern Natural Gas

State Geological Survey
WICHITA, BRANCH

S. 8 T. 35S R. 33W E
Loc. NW SE
County Seward County



Elev.: Gr. 2850
DF 2860 KB 2862

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1517	65-35 poz	700	1/4#/sx flake, 6% 2% CaCl ge
Production	7 7/8"	4 1/2"	10.5	6349	50-50 poz	300	2% gel, 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft. 4 SPF	Size & type Jet	Depth interval
					6244-53'
					6213-20'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	6243'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac'd w/47,000# 10/20 sd in gelled water	6213-20'
Acidized w/3000 gal 15% MCA w/ 24 7/8" ball sealers	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
1/17/81	Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbis.	317 MCF	0 bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)
Sold	6213-20'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

7-9-86 1111 - 9 1986

Operator Rincon Operating Co. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas Well

Well No. 1 Lease Name Parsons Jones

S 8 T 35S R 33WE W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 6210-6350'			Morrow	5921'
Open 30" SI 60"				
Open 60" SI 60"			Low Morrow	6161'
Rec'd 240' GCM			Chester	6215'
IHP 3179#, IFP 45-45#, ISIP 1673#, FFP 26-45#, FFP 26-45#, FSIP 1745#, FHP 3179#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>C. A. Hansen</i> Signature: C. A. Hansen Mgr Drlg & Prod Title 2/13/81 Date</p>
---------------	---

RECEIVED
STATE CORPORATION COMMISSION

JUL - 9 1986

CONSERVATION DIVISION