

JURY NO. 2  
Panhandle Development Company, Inc.  
Section 26-33s-31w  
Seward County, Kansas

Casing Record

Commenced: 12-26-1961  
Completed: 1-17-1962

Ran 39 joints of new 8 5/8" O.D. casing, set at 1245.52 G.L. Cemented with 650 sacks H.A.5. Ran 189 joints of 5 1/2" O.D. casing, set at 5924' K.B. Cemented with 125 sacks of salt saturated cement.

Formation:	From	To
Surface soil and sand	0'	100'
Sand and clay	100	290
Shale and sand	290	580
Red bed and shells	580	1000
Shale and shells	1000	1260
Red Bed	1260	1300
Red bed and shale	1300	1450
Anhydrite	1450	1505
Shale	1505	1910
Shale and anhydrite	1910	2248
Shale and lime	2248	2885
Lime	2885	3220
Lime with chalk	3220	3510
Lime	3510	3635
Lime and chalk	3635	3720
Lime	3720	3920
Lime and shale	3920	4285
Lime	4285	5489
Lime and shale	5489	5617
Lime	5617	5925 RTD

NOTARY PUBLIC  
JUN 23 1978  
6-23-78  
Seward, Kansas

State of Kansas }  
County of Seward } SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Jury No 2 well, located C-NE-NW of Section 26-33s-31w, Seward County, Kansas.

McCLELLAN DRILLING COMPANY

by *[Signature]*

Subscribed and sworn to before me a notary public this 22 day of January 1962.



*[Signature]*  
Notary Public

My Commission Expires:

September 16, 1964