

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Monsanto Company

API NO. 15-095-21148 -00-00

ADDRESS 3545 NW 58th Street

COUNTY Kingman

Oklahoma City, Oklahoma 73112

FIELD Spivey Grabs

**CONTACT PERSON Bruce E. Roll

PROD. FORMATION Miss. Chat

PHONE (405) 947-2361

LEASE Render

PURCHASER Koch

WELL NO. 4

ADDRESS P. O. Box 2256

WELL LOCATION Se of SW

Wichita, Kansas 67201

660 Ft. from South Line and

DRILLING H-30 Drilling, Inc.


660 Ft. from East Line of

CONTRACTOR 251 N. Water

the SW/4 SEC. 5 TWP. 30S RGE. 7W

ADDRESS Wichita, Kansas

PLUGGING CONTRACTOR ADDRESS



WELL FLAT

KCC
 KGS
 MISC
 (Office Use)

TOTAL DEPTH 4370 PBDT -----

SPUD DATE 9-15-81 DATE COMPLETED 11-24-81

ELEV: GR 1500 DF 1506 KB 1508

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|--------------|-------|----------------------------|
| Surface | 12 1/4" | 8 5/8 | 24 | 259 | Class H | 300 | 2% gel, 3% cacl. |
| Production | 7 7/8" | 5 1/2 | 15.5 | 4370 | 50/50 Pozmix | 200 | 2% gel, 18% salt |
| | | | | | | | |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth Interval |
|----------|-------------|--------------|---------------|-------------|----------------|
| None | | | | | 4204-4208 |
| | | | | | 4176-4190 |
| | | | | | 4170-4171 |

TUBING RECORD

| Size | Setting depth | Packer set at |
|--------|---------------|---------------|
| 2 7/8" | 4266 | None |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

STATE CORPORATION COMMISSION

Amount and kind of material used

Depth interval treated:

| | |
|---|-----------|
| 750 gallons 15% | 4204-4208 |
| 1500 gallons 15%; 40,000 gallons 3% gel | 4204-4208 |
| | 4176-4190 |
| | 4170-4171 |
| | 4152-4166 |

Date of first production 11-24-81 Producing method (flowing, pumping, gas lift, etc.) Pumping Gravity

RATE OF PRODUCTION PER 24 HOURS Oil Not Tested Gas Water % Gas-oil ratio

Disposition of gas (vented, used on lease or sold) Used on Lease but will be sold later Perforations 4152'-4208' (OA)

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

710 230
 NOV 24 1981

Name of lowest fresh water producing stratum ----- Depth 100'

Estimated height of cement behind Surface Pipe Circulated.

DV USED? No

WELL LOG

| Formation Description, Contents, etc. | Top | Bottom | Name | Depth |
|---------------------------------------|------|--------|-----------|-------|
| Red Beds | 0 | 291 | Beren | 2530 |
| Red Beds & Shale | 291 | 1440 | Topeka | 2752 |
| Lime & Shale | 1440 | 4370 | Heebner | 3144 |
| Total Depth | | 4370 | Douglas | 3176 |
| | | | Lansing | 3366 |
| | | | Marmaton | 3882 |
| | | | Cherokee | 4038 |
| | | | Miss Chat | 4152 |
| | | | Miss Lime | 4224 |
| | | | T. D. | 4370 |

A F F I D A V I T

STATE OF Oklahoma, COUNTY OF Oklahoma SS, _____

Bruce E. Roll OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Regional Production Manager (FOR) ~~(OF)~~ Monsanto Company

OPERATOR OF THE Render LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 4 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 25th DAY OF November, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) Bruce E. Roll

SUBSCRIBED AND SWORN BEFORE ME THIS 25th DAY OF November 19 81

Julie Forbes
NOTARY PUBLIC

MY COMMISSION EXPIRES: 8-31-85