

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. BOX 17027  
Wichita, Kansas 67217  
NORTH

Kiowa County. Sec. 22 Twp. 29 Rge. (E) 18 (W)

Location as "NE/CNW/SE/SW" or footage from lines C SE SW

Lease Owner Misco Industries, Inc.

Lease Name Frank Yohn Well No. 2

Office Address 257 N. Broadway, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed June 7 1974

Application for plugging approved June 10 1974

Plugging commenced July 24 1974

Plugging completed Aug. 22 1974

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	393'	10"	393'	none
			4912'	7"	4912'	2667.63

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4100' and dumped 6 sacks of cement.

Set 10' rock bridge at 200' and plugged well with 4 yards of ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1974

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC. (If additional description is necessary, use BACK of this sheet)

Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss. Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1974

My commission expires July 16, 1978

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS

Notary Public.

15-097-10141-0000

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- OHIO OIL CO.  
Farm- Frank Yohn No. 2

SEC. 22 T. 29 R. 18W  
C SE SW

Total Depth. 4940'  
Comm. 7-4-57 Comp. 8-5-57  
Shot or Treated.  
Contractor. Falcon-Seaboard Drig.  
Issued. 12-7-57

County Kiowa KANSAS



CASING:  
10 3/4" 393'  
7" 4927'

Elevation. 2184' RB

Production. I.P. 105 BO & 6 BW

Figures indicate Bottom of Formations.

- red bed, shale & clay 356
- red bed 870
- red bed & shale 2254
- shale & Anhydrite 2436
- shale & lime 2678
- lime 2933
- lime & shale 3207
- shale 3320
- lime & shale 3568
- shale 3652
- lime 3746
- lime & shale 3820
- lime 3863
- shale & lime 4110
- shale 4267
- lime 4428
- lime & shale streaks 4470
- lime 4507
- lime & shale 4593
- lime 4637
- lime & shale 4675
- lime 4768
- lime & shale 4915
- lime & chert 4940
- Total Depth

- TOPS:
- Brown Lime 4262
- Lansing-Kansas City 4274
- Mississippi Chert 4898

Show of gas and oil from 4898' to 4939'.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas