

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Kiowa County. Sec. 7 Twp 29S Rge. 19 (E) 19 (W)

Location as "NE/CNW\*SW\*" or footage from lines 668.5' FSL & 1980.4' FEL

Lease Owner Anadarko Production Company

Lease Name Brown "F" Well No. 1

Office Address Box 351, Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-25, 19 70

Application for plugging filed 12-2, 19 70

Application for plugging approved 12-1, 19 70

Plugging commenced 11-25, 19 70

Plugging completed 11-25, 19 70

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein Attica, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5250 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 670'   | NONE       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 45 sacks cement 650' to 500'.

Spotted 15 sacks cement 40' to surface.

Hole filled with mud between plugs.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 - 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bowers Drilling Company  
Address Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEWARD, ss.


V. K. DOWNEY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey

Box 351, Liberal, Kansas 67901  
(Address)

SUBSCRIBED and SWORN to before me this 2 day of December, 19 70



My commission expires My Commission Expires April 28, 1971

T. W. Williams  
Notary Public.

DRILLER'S LOG

WELL NAME Brown "F" No. 1 COMPANY OPERATING Anadarko Production Company  
 ADDRESS OF COMPANY Box 351, Liberal, Kansas 67901

WELL LOCATION  $\frac{1}{4}$   $\frac{1}{4}$   $\frac{1}{4}$   
668.5 Ft. North of South Line,  
3268.6 Ft. East of West Line, Sec. 7, Twp. 29S, Rge. 19W, Kiowa County, Kansas

DRILLING STARTED 11-12, 19 70, DRILLING COMPLETED 11-25, 19 70  
 WELL COMPLETED 11-25, 19 70, WELL CONNECTED \_\_\_\_\_, 19 \_\_\_\_\_

ELEVATION \_\_\_\_\_ Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Dry Hole

| OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION |      |    |              |              |           |
|---|------|----|--------------|--------------|-----------|
| Name  | From | To | No. of Shots | Gallons Used | Kind Used |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |
|   |      |    |              |              |           |

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 4 - 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

CASING RECORD

| Size   | Amount Set | Sacks of Cement | Amount Pulled |
|--------|------------|-----------------|---------------|
| 8 5/8" | 670'       | 400             | NONE          |
|        |            |                 |               |
|        |            |                 |               |
|        |            |                 |               |

FORMATION RECORD

| Formation      | Top  | Bottom | Formation    | Top  | Bottom |
|----------------|------|--------|--------------|------|--------|
| Clay & Sand    | 0    | 120    | Shale & Lime | 3857 | 4000   |
| Sand           | 120  | 335    | Lime         | 4000 | 4145   |
| Sand & Shale   | 335  | 414    | Lime & Shale | 4145 | 4360   |
| Shale          | 414  | 700    | Lime         | 4360 | 5250   |
| Shale & Shells | 700  | 1094   | Total Depth  | 5250 |        |
| Shale          | 1094 | 2245   |              |      |        |
| Shale & Lime   | 2245 | 2495   |              |      |        |
| Lime & Shale   | 2495 | 2638   |              |      |        |
| Lime           | 2638 | 2920   |              |      |        |
| Shale & Lime   | 2920 | 3050   |              |      |        |
| Lime & Shale   | 3050 | 3565   |              |      |        |
| Shale & Lime   | 3565 | 3670   |              |      |        |
| Lime & Shale   | 3670 | 3857   |              |      |        |

RESULTS OF INITIAL PRODUCTION TEST: D & A