


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 5 Twp. 29 Rgs. 19 (E) (W)
Location as "NE/CNW/SE" or footage from lines. C SE SE
Lease Owner Raymond Oil Co., Inc.
Lease Name Porter #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1/3/74 19
Plugging completed 1/11/74 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 5080 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	610	none
				5 1/2"	5114	2905'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4950' and dumped 5 sacks cement.
Shot pipe at 4311', 4218', 4128', 4035'. Allied pumped 40
barrels oil, chased plug to 4000'. Shot pipe at 3848', 3751',
3655', 3562', 3280', 3185', 3093', 2966', pulled 90 joints.
Set 10' rock bridge at 210' and dumped 25 sacks cement. Mud to
40', 10' rock bridge and capped with 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1974

CONSERVATION DIVISION

Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 14th day of January, 1974

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

DRILLERS LOG

No. 1 Porter

CASING RECORD:	COMPANY:	Raymond Oil Company	DESCRIPTION:
8 5/8" @ 610' w/475 sx cement	CONTRACTOR:	Red Tiger Drilling Company	C/SE SE 5-29S-19W Kiowa County, Kansas
5 1/2" @ 5114' w/175 sx cement	COMMENCED:	November 3, 1969	
	COMPLETED:	November 21, 1969	
TOTAL DEPTH: 5116'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod & Sand	0	180	
Shale	180	490	
Sand	490	515	
Shale	515	610	
Red Bed, Shale	610	643	
Blaine Anhydrite	643	659	
Shale	659	1530	
Shale & Lime	1530	1755	
Shale	1755	2167	
Anhydrite	2167	2255	
Shale	2255	2350	
Shale & Lime	2350	4420	
Lime	4420	4856	
Lime & Shale	4856	5096	
Chert	5096	5116	


RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 25th day of November, 1969.



Gloria Fawcett
Notary Public

My Commission Expires:

10/25/72