

1091026

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,193-0000
C SE SW SEC. 35, T 29 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION

350 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

2130 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHMIDT C WELL # 2

TECHNICIAN'S PLUGGING REPORT

11/30

COUNTY KIOWA 168.42

OPERATOR LICENSE # 5004

WELL TOTAL DEPTH 5182 FEET

OPERATOR: VINCENT OIL CORPORATION

PRODUCTION CSG: SIZE 4 1/2" @ 5182' WITH 100 SX

NAME AND 125 N MARKET #1075

SURFACE CASING: SIZE 8 5/8" @ 650' WITH 175 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 30 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 5047-52

1ST PLUG SAND TO 4970' WITH 4 SX CEMENT ON TOP. 2ND PLUG PULL CASING TO 1250' AND SPOT 10 SX GEL, 7 HULLS, AND 50 SX CEMENT. 3RD PLUG PULL TO 675' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' SPOT 10 SX CEMENT. WELL STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 30 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4970' WITH 4 SX CEMENT ON TOP. 2ND PLUG PULL CASING TO 1250' SPOT 10 SX GEL, 7 HULLS, & 50 SX CEMENT. 3RD PLUG PULL TO 675' AND SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' AND SPOT 10 SX CEMENT. WELL STAYED FULL.

DEC 08 1999
12-8-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 12/23/99
INV. NO. 061036

SIGNED (TECHNICIAN) FORM CP-2/3

CONSERVATION DIVISION
KANSAS CORPORATION COMMISSION
RECEIVED
DEC 08 1999
12-8-99
[Signature]