

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097 -20,995-0000

N/2SW NE, Sec. 36, T 29 S, R 19 W/X

1650 feet from N/S section line

1980 feet from ~~W/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Yost Farms Well # 2

Operator: TXO Production Corp.
Name & 200 West Douglas, Suite 300
Address Wichita, KS 67202

County Kiowa

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 596

165.75

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling, Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 10:00 pm Day: 7 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Gerald Veatch

(company name) FWA Drilling (phone) _____

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1200' with 50 sx cement,

2nd plug at 630' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 am Day: 8 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 630' with 40 sx cement, 3rd plug & 4th plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th & 6th plugs to circulate rathole and mousehole with 10 sx cement each.

Remarks: Use 60/40 Pozmix with 2% gel, 3% cc.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~xxx~~ / did not) observe this plugging.

INVOICED

DATE 2-15-84

INV. NO. 0244

2-8

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)