

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20959-00-00
Spot: CN2N2NE Sec/Twnshp/Rge: 36-29S-19W
4950 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: YOST FARMS Well Number: 1
County: KIOWA Total Vertical Depth: 5066 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/64.65
Surface Casing: Size 8.625 feet: 604 WITH 175 SX CMT
Production: Size 4.5 feet: 5065 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/23/2002 10:55 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4800' WITH 4 SX CMT ON TOP. 1ST PLUG AT 1200' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/23/2002 12:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 4884-90'. SAND TO 4800' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1200' & PUMP 10 SX GEL - 50 SX CMT. 2ND PLUG PULL CASING TO 640' & PUMP 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.


RECEIVED
5-25-2002
MAY 28 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2832' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

INVOICED MAY 23 2002

DATE 5-30-02

INV. NO. 2002061856

Form 09-23