

1041407

STATE CORPORATION COMMISSION

API NUMBER 15-097-21454-0000
W/2W/2 SW SW SEC. 27, T 29 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4840 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HAYS WELL # 1

TECHNICIAN'S PLUGGING REPORT

4/19

COUNTY KIOWA 155.03

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4770 FEET

OPERATOR: OIL PRODUCERS, INC OF KS. PRODUCTION CSG: SIZE 4 1/2" @ 5239' WITH 125 SX

NAME AND PO BOX 8647 SURFACE CASING: SIZE 8 5/8" @ 642' WITH 230 SX

ADDRESS WICHITA, KS 67208-0647

ABANDONED OIL WELL XX GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR. STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 07 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCNTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 5114-5123

1ST PLUG SANDED TO 5037' AND 4 SX CEMENT. FILL HOLE WITH MUD. 2ND PLUG AT 1250' WITH

50 SX CEMENT. 3RD PLUG PULL TO 670' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' FILL WITH

10 SX CEMENT. STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE PFIEFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 7/19 MONTH: 7/04 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 5037' AND 4 SX CEMENT. FILL HOLE WITH MUD. 2ND PLUG AT 1250' WITH

50 SX CEMENT. 3RD PLUG PULL TO 670' SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40' FILL WITH

10 SX CEMENT. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 2000

7-17-2000

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3652 OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 7/18/00 SIGNED Steve Pfeifer

(TECHNICIAN)

FORM CP-2/3

INV. NO. 1060076