

1 080340

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,690 - 0000

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
4620 feet from E section line

Operator License # 5427

Lease Name Coolidge Well # 1

Operator: D. R. Lauck Oil Co., Inc.
Name & Address: 221 South Broadway, Suite 400
Wichita, KS 67202

County Kiowa 169.33
Well Total Depth 5210 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 659

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 12 Month: March Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5204 PBDT 5136' Perfs at 5123-5129

1st plug sand back to 5070' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug, and pump 170 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 pm Day: 12 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5070' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 170 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1985

3-15-85
CONSERVATION DIVISION

Maximum pressure 500 psi and shut in 50 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 3300 Wichita 1 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-18-85

INV. NO. 7365

3-12

Signed J. R. Mey (TECHNICIAN) SR