

To: 1 051631  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-24

API NUMBER 15-097-20,542A

C NE SE, SEC. 30, T 29 S, R 19 WXX

1980 feet from S section line

660 feet from E section line

Lease Name Eagle Canyon Ranch Well # 1

County Kiowa

Well Total Depth 5148 167.31 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 559

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Operator: J. Mark Richardson

Name & Address 155 N. Market, Ste. 840

Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J. Mark Richardson License Number 5414

Address 155 N. Market, Ste. 840, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 24 Month: 3 Year: 19 93

Plugging proposal received from Carl Shield

(company name) J. Mark Richardson (phone) 316-723-2204

were: 4 1/2" at 5145' w/225 sx cement, PBTD 5111', Perfs at 5080-88'

1st plug sand back to 5040' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 a.m. Day: 24 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 5030' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3551' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form) observe this plugging.

INVOICED

DATE 3-31-93

WELL NO. 37525 3-24

Signed Richard W. Lyon (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAR 26 1993

CONSERVATION DIVISION Wichita, Kansas