

1 060707

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,815 - 0000

C SE SE SEC. 21, T 29 S, R 19 W/E

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Rose Well # 1-21

Operator: GRAHAM-MICHAELIS CORPORATION  
Name &

County Kiowa 169.33

Address P.O. BOX 247 Wichita, Kansas 67201

Well Total Depth 5210 feet

Conductor Pipe: Size 2-5/8 feet

Surface Casing: Size 8-5/8 feet 627

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent Casing Pulling Co. License Number 6547

Address P.O. Box 506, Liberal, Kansas 67901

Company to plug at: Hour: 9:00A. Day: 1 Month: November Year: 1985

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4-1/2" at 5209' PBD 5165' Perfs at 5117 to 5122 Spot through 4-1/2 with heavy mud between Plugs. 1st. Plug Pumped to bottom with 1 sx. hulls and 25 sx. cement

2nd plug at 1300' with 40 sx cement

3rd Plug at 660' with 50 sx cement

4th Plug at 40' to 0' on solid bridge with 10 sx cement They recovered 4014' of 4-1/2 production pipe.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 P.M. Day: 1 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st. Pumped 1 Sx hulls and 25 sx cement to Bottom covering perfs.

2nd shot off pipe at 4014 and pulled pipe to 1300' and pumped 40 sx of cement.

3rd plug pulled pipe to 660' and pumped 50 sx cement.

4th plug made solid bridge at 40' and pumped 10 sx cement filling the 8-5/8 to 5' below ground level.

Remarks: Sargent's Pumped common cement.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-85

INV. NO. 11333

observe this recording.  
STATE CORPORATION COMMISSION

NOV 5 1985

Signed Paul A. Luthi  
(TECHNICIAN)