

1 070346

MAY 20 1987

API NUMBER 15- 097-21,236-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SE, SEC. 13, T 29 S, R 19 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Unruh Grey Well # 6
County Kiowa 167.05

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

Well Total Depth 5140 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 748

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 20 Month: 5 Year: 19 87

Plugging proposal received from Rick Davis

(company name) H-30 Inc. (phone) 316-793-3687

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2336' Anhydrite 1265-1300'

1st plug at 1300' with 50 sx cement, 2nd plug at 780' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 a.m. Day: 20 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1300' with 50 sx cement,

2nd plug at 780' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement.

Remarks: Used 60/40 Pozmix 4% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-27-87

INV. NO. 17008

Signed Dan Johnson

(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
5-26-87
MAY 26 1987

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Expected Spud Date April 20, 1987
month day year 1987

(see rules on reverse side)

API Number 15- 097-21,236-0000

OPERATOR: License # 5171
 Name TXO Production Corp.
 Address 155 N. Market, Suite 1000
 City/State/Zip Wichita, Kansas 67202
 Contact Person Jeffrey S. Childs
 Phone (316) 269-7662

C NW SE Sec. 13 Twp. 29S Rg. 19 X West
 1980' FSL
 1980' FEL
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107
 Name H-30 Inc.
 City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 1980' feet
 County Kiowa
 Lease Name UNRUH GREY Well # #6
 Ground surface elevation 2336' feet MSL
 Domestic well within 530 feet: yes X no
 Municipal well within one mile: yes X no
 Depth to bottom of fresh water 200'
 Depth to bottom of usable water 200'
 Surface pipe by Alternator: 1 X 2
 Surface pipe planned to be set 250'
 Conductor pipe required none
 Projected Total Depth 5050' feet
 Formation Pawnee

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj. X Pool Ext. Air Rotary
OWWO Expl. Wildcat Cable

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging back to specifications.
 Date 4-3-87 Signature of Operator or Agent Jeffrey S. Childs Title Drig. & Prod. Engineer

For KCC Use:
 Conductor Pipe Required 250 feet; Minimum Surface Pipe Required 250 feet per Alt.
 This Authorization Expires 10-20-87 Approved By 4-20-87

5-4-87
Move in

8 5/9 200'

C NW SE Sec. 13 Twp. 29S Rg. 19 XX East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 1100' Ann. or formation with 50. SXS feet of 60/40 Poz
 2nd plug @ ft. deep 300' or formation with 50. SXS feet of " "
 3rd plug @ ft. deep 40' or formation with 10. SXS + bridge feet of " "
 4th plug @ ft. deep or formation with feet of " "
 5th plug @ ft. deep or formation with feet of " "

(2) Rathole to surface minus 5 feet 10 SXS (b) Mousehole to surface minus 5 feet 10 SXS

PUSHER Rick Davis
5140' FORMATION MISS
 SURFACE PIPE 8 5/8" @ 748'
 ANHYDRITE 1265' ELEVATION 2336
1300' 5-10-87
 STARTING TIME & DATE 7:00 AM
 COMPLETION TIME & DATE 8:30 AM 5-20-87
 1st PLUG @ 1300 FT. W/ 50 SX
 2nd PLUG @ 780 FT. W/ 50 SX
 3rd PLUG @ 40 FT. W/ 10 SX
 4th PLUG @ FT. W/ SX
 RAT HOLE CIRCULATED W/ 10 SX
 MOUSE HOLE CIRCULATED W/ SX
 WATER WELL PLUGGED W/ 10 SX
 CEMENT COMPANY Halliburton
 TECHNICIAN Lacey, D.G.

60/40poz
no one saw 4/9/87
 RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1987
 CONSERVATION DIVISION
 Wichita, Kansas