

4-14-88

96 R

API NUMBER 15-097-21,125 - 0000

1 061097

Tq.
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 SE, SEC. 13, T 29 S, R 19 W/8

330 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Unruh-Grey Well # 5

Operator: TXO Production Corporation

County Kiowa 164.13

Name & Address 155 North Market, Suite 1000

Well Total Depth 5050 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 4 p.m. Day: 14 Month: 4 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5046' PBTD 4790' Perfs at 4796-4800'

1st plug sand back to 4740' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 2 sx gel, 100 sx econolite cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 14 Month: 4 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4740' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 2 sx hulls, 2 sx gel, and 100 sx econolight cement.

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used econolight cement by P. J. Pittan. Recovered 3400' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-26-88

INV. NO. 20473

4-14

RECEIVED APR 19 1988 CONSERVATION DIVISION Wichita, Kansas

Signed Paul A. Luthie (TECHNICIAN)