

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20680-00-01  
Spot: CSEnw Sec/Twnshp/Rge: 14-29S-19W  
1980 feet from N Section Line, 2010 feet from W Section Line  
Lease/Unit Name: HEINZE A OWWO Well Number: 1  
County: KIOWA Total Vertical Depth: 3765 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 125 N. MARKET, STE 1075  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 681 WITH 400 SX CMT  
Production: Size 4.5 feet: 3658 WITH 125 SX CMT  
Liner: Size feet: \$122.36

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/06/2001 2:00 PM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC  
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL CORPORATION Phone: (316) 546-3316

Proposed Plugging Method: CIBP @ 3520' & 2 SX CMT. 1ST PLUG AT 1380' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 08/06/2001 4:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 3649'. PERFS AT 3571-3576'. 1ST PLUG CIBP @ 3520' WITH 2 SX CMT ON TOP. 2ND PLUG PULL CASING TO 1380' AND SPOT 15 SX GEL & 50 SX CMT. 3RD PLUG PULL TO 700' AND SPOT 50 SX CMT. 4TH PLUG PULL TO 40' AND SPOT 10 SX CMT TO SURFACE. STAYED FULL.

RECEIVED  
AUG - 9 2001  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 4 1/2" CASING.

Plugged through: CSG

**INVOICED**  
DATE 8-13-01  
INV. NO. 2002060220

District: 01

Signed - 

(TECHNICIAN)

AUG 07 2001

Form CP-2/3

