

15-097-30107-0001

Docket No. A-12,370

API NUMBER 15- Completed 4-7-66

To: 1 010105
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

C SE SW, SEC. 11, T 29 S, R 19 W/EX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5375Lease Name Unruh Well # 2 SWDOperator: Hillenburg Oil Co.County Kiowa 163.77Name & Address 116th & South Lynn LaneWell Total Depth 5039 feetBroken Arrow, OK 74012Conductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 635Abandoned Oil Well Gas Well Input Well SWD Well X D&A Other well as hereinafter indicated Plugging Contractor Hillenburg Oil Co. License Number 5375Address 116th & South Lynn Lane, Broken Arrow, OK 74012Company to plug at: Hour: 1:20 pm Day: 11 Month: March Year: 19 86Plugging proposal received from Charles McMannis(company name) Hillenburg (phone) 913-483-5750were: 4 1/2" at 5041' Perfs at 5042-52'

Pump 2 sx hulls, 30 sx cement, 23 sx gel, release 4 1/2" rubber plug and pump 100 sx cement.

Pump 100 sx cement down annulus

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None Operations Completed: Hour: 2:10 pm Day: 11 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Pumped 2 sx hulls, 30 sx cement, 19 sx gel, released 4 1/2" rubber

plug and pumped 100 sx cement - Maximum pressure 1400 psi and shut in 800 psi

2nd plug pumped 100 sx cement down backside - Maximum pressure 0 and shut in 0

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

STATE CORPORATION COMMISSION

Signed Jack L. Durrant

(TECHNICIAN)

DATE APR 1 1986INV. NO. 13210

APR 3 1 1986

APR 10 1986

CONSERVATION DIVISION
Wichita, Kansas

RCD 3-31-86

FORM CP-2/3
Rev. 01-84