

To: 1 100067  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 1/31/45 - spud date  
NE NE NE SW, SEC. 28, T 29 S, R 35 W/E  
2540 feet from S section line  
2740 feet from E section line

10-2  
TECHNICIAN'S PLUGGING REPORT  
Operator License # 4824  
Operator: Mesa Operating Co.  
Name:  
Address 5205 N. O'Connor, Ste. 1400W  
Irving, TX 75039

Lease Name T.J. Lahey Well # 1  
County Grant 87.58  
Well Total Depth 2695 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 680

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SNO Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt.1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11:30 a.m. Day: 1 Month: 10 Year: 19 96

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone #) 05-854-6515

was: 7" at 2503' w/125 sx cement, 5 1/2" slotted liner at 2695' to 2473', Perfs at 2450-2664'

1st plug pump 100 sx cement at cut off point,

2nd plug pull to 725' and pump 100 sx cement,

3rd plug pull to 350' and pump 50 sx cement, 4th plug pull to 35' and pump 20 sx cement,

5th plug run 1" tubing outside 10 3/4" surface pipe, cement to surface with cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 2 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 10/1/96 1st plug set 100 sx cement at 1066',

2nd plug pulled to 725' and set 80 sx cement,

10/2-3rd plug pulled to 350' and set 50 sx cement,

4th plug pulled to 35' and set 20 sx cement to 3',

5th plug ran 1" outside 10 3/4" surface to 35'. Cemented to surface with 20 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 1066' of 7" casing.  
(if additional description is necessary, use BACK of this form.)

observe this plugging.

Signed: Gary Winters (TECHNICIAN)

INVOICE  
OCT 17 1996  
DATE  
WVZ NO. 46712

RECEIVED  
SAS  
CORP  
DOM  
OCT 9 1996  
P 2:09  
RCD 10-9-96