

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21283-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 35-29S-35W
1930 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: MLP NICEWANDER A Well Number: 1
County: GRANT Total Vertical Depth: 5800 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1805 WITH 675 SX CMT 488.50
Production: Size 5.5 feet: 5798 WITH 935 SX CMT
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/08/2001 12:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS - 25 SX CMT - MUD SPACER TO 1830'. PUMP 25 SX CMT AT 1830'. CMT FROM 800-0'.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/08/2001 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 5605'. PERFS AT 5548-5477'. 2ND STAGE DONE. PUMPED 425 SX CMT AT 3000'. CIRCULATED TO SURFACE. 1ST PLUG PUMP 6 SX HULLS & 25 SX CMT, DISPLACE WITH 75.5 BBLS OF MUD TO 1830'. 2ND PLUG PUMP 25 SX CMT, DISPLACE WITH MUD TO 800' WITH 18.5 BBLS. 3RD PLUG CMT TO SURFACE FROM 800' TO 91 SX CMT.

INVOICED
DATE 5-14-01
TWN. NO 200106.1797

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed 
RECEIVED
(TECHNICIAN)
KANSAS CORPORATION COMMISSION

MAY 14 2001 MAY 11 2001

CONSERVATION DIVISION 

Form  2/3