

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20478-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 35-29S-35W
2590 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: LOWE Well Number: 2-35
County: GRANT Total Vertical Depth: 2950 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

Production Casing Size: 5.5 feet: 2952 WITH 600 SX CMT
Surface Casing Size: 8.625 feet: 674 WITH 400 SX CMT

\$ 95.88

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/02/2003 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. DISPLACE WITH MUD. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/05/2003 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 2934'. PERFS AT 2843-2913'. TOC @ 570'. PUMP 400# HULLS WITH 25 SX CMT. DISPLACE WITH MUD. LOAD HOLE WITH MUD. 1ST PLUG PUMP 50 SX CMT AT 540'. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 40'. SDON. 05/05/03: LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
MAY 19 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 540' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART# _____
(TECHNICIAN)

INVOICED

DATE 5-20-03

INV. NO. 2003061541

Form CP-23