

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00115-00-00
Spot: NWNWE Sec/Twnshp/Rge: 25-29S-36W
2540 feet from S Section Line, 2540 feet from E Section Line
Lease/Unit Name: RENO S A Well Number: 1-25
County: GRANT Total Vertical Depth: 2715 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

Production Casing Size: 7 feet: 2715 WITH 450 SX CMT
Surface Casing Size: 10.75 feet: 621 WITH 100 SX CMT

B 88.24

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/13/2003 10:20 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DAVE HIGGINS Company: PIONEER NATURAL Phone: (972) 444-9001

Proposed Plugging Method: PUMP 100# HULLS & 80 SX CMT ON BOTTOM. LOAD WITH MUD. PLUG AT 890' WITH 50 SX CMT. PLUG AT 650' WITH 80 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/13/2003 4:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 2462-2682'. PUMP 1100# HULLS & 80 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG PULL TO 890' & SPOT 50 SX CMT. 2ND PLUG PULL TO 650' & SPOT 85 SX CMT. 3RD PLUG PULL TO 30' & SPOT 15 SX CMT. STAYED FULL.


RECEIVED
MAY 19 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 920' OF 7" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY 14 2003
KCC Dodge City

Signed 
(TECHNICIAN)

INVOICED
DATE 5-20-03
INV. NO. 2003061541

Form CP-203
