

1060154

TO: STATE CORPORATION COMMISSION
API NUMBER 15-097-21,439-0000
100'W 35'S NE NE SW SEC. 20, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 2275 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2210 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME NICHOLS WELL # 1-20

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA 176.80

OPERATOR LICENSE # 5004 WELL TOTAL DEPTH 5440 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE " FEET

NAME AND ADDRESS 125 N MARKET, SUITE 1075 SURFACE CASING: SIZE 8 5/8" @ 359' WITH SX

WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 06 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:

1ST PLUG AT 5340' WITH 50 SX CEMENT. 2ND PLUG AT 1180' WITH 80 SX CEMENT.

3RD PLUG AT 370' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 06 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 5340' WITH 50 SX CEMENT. 2ND PLUG AT 1160' WITH 80 SX CEMENT.

3RD PLUG AT 370' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4" FLO SEAL BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
I DID NOT OBSERVE THIS PLUGGING.
RECEIVED
STATE CORPORATION COMMISSION
DATE APR 16 1999 4-13-1999

SIGNED Michael J. Maier
(TECHNICIAN) FORM. CP-2/3

INV. NO. 60853
APR 13 1999
CONSERVATION DIVISION