

To: 1 060731  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,194-0000  
CNESE, SEC. 15, T 29 S, R 18 W/4  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004  
Operator: Vincent Oil Corp.  
Name &  
Address 125 N. Market Suite 1110  
Wichita, Kansas  
67202

Lease Name Dargel Fruit Well # 2  
County Kiowa 159.58  
Well Total Depth 4910 Mississippi feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 516

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated any <sup>top 1084</sup> ~~Base~~ 1095

Plugging Contractor Wheat States Oil Field Service License Number 5149

Address Pratt, Kansas 67124

Company to plug at: Hour: 11:20 AM Day: 22 Month: November Year: 19 85

Plugging proposal received from Norman Hagan

(company name) Wheat States Oil Field Service (phone) 316-672-7514

were: 1st plug @ base of anhydrite w/ 50 sbx cement.

2nd plug @ 30' out of surface w/ 50 sbx cement.

3rd plug @ 40' on solid bridge w/ wood plug w/ 10 sbx cement filling hole to 0'

4th <sup>5th</sup> plug @ circulate 10 sbx cement in rat hole & 10 sbx cement in mouse

hole. Recommended 60/40 press mix w/ 6% yell.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 PM Day: 22 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st - Filled hole w/ heavy mud before pumping  
each plug. Pumped cement through drill pipe.

1st plug @ 1095' w/ 50 sbx cement. 2nd plug @ 547' w/ 50

sbx cement. 3rd plug on solid bridge w/ hulls & wood plug &

pumped 10 sbx cement filling hole to 0'. Circulated 10

sbx cement in each the rat & mouse holes. B.J. Litten

Remarks pumped 60/40 press mix w/ 6% yell.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.  
STATE CORPORATION COMMISSION  
12-2-85

Signed Paul A. Luthi  
(TECHNICIAN)

DATE DEC 10 1985

DEC 2, 1985

INV. NO. 11392

CONSERVATION DIVISION



**Oilfield Services, Inc.**

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Dargel Trust #2  
 C NE SE Sec. 15-29S-18W  
 Kiowa County, Kansas  
 Commenced: 11-11-85  
 Completed: 11-22-85  
 API #15-097-21,194  
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	480	Sand, Red Bed	Ran 12 joints (503.39') new, 23#, 8 5/8" surface casing. Set at 516.39 with 200 sxs lite, 3% cc and 100 sxs Class A, 3% cc, 2% gel. Cement did circulate. Plug down at 3:30 a.m. on November 12, 1985. Job by B. J. Titan, Medicine Lodge, Kansas.
480	900	Red Bed	
900	2061	Red Bed, Shale	
2061	4910	Lime, Shale	
		T.D.	

RTD 4910'

Plugged well with 130 sxs 60/40 poz, 6% gel as follows: 1105'-50 sxs; 557'-50 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs; mousehole-10 sxs. Plug down at 1:00 p.m. on November 22, 1985. Job by B.J. Titan, Medicine Lodge. State plugger out of the Dodge City, Kansas office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, PRESIDENT



*Mary L. Tjaden*  
 NOTARY PUBLIC RECEIVED STATE CORPORATION COMMISSION

My Commission Expires:  
3/22/88

DEC 4 1985

CONSERVATION DIVISION  
 Wichita, Kansas