

1 080231.

API NUMBER 15- 097-21,062-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C NE SE NW, SEC. 9, T 29 S, R 18 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3630 feet from N SE Corner of  
2970 feet from W SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Graves Well # 1

Operator: Vincent Oil Corporation  
Name & Address: 125 North Market, Suite 1110  
Wichita, KS 67202

County Kiowa  
Well Total Depth 5030 163.48 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 498

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 10:00 am Day: 6 Month: October Year: 19 84

Plugging proposal received from Roger Baker

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1200' with 50 sx cement

2nd plug at 540' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement. Plug water well with 5 sx cement  
Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:55 am Day: 6 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 540' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to  
circulate mouse hole with 10 sx cement and plugged water well with 5 sx cement

RECEIVED  
OCT 12 1984  
10-12-84  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie  
(if additional description is necessary, use BACK of this form.)

(not to be observed) observe this plugging.

INVOICED

Signed J. H. Metz (TECHNICIAN) SD

DATE 10-15-84

INV. NO. 4324