

To: 1 040782  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-15 API NUMBER 15- 097-21,223-0000  
W/2. NE NW, SEC. 10, T 29 S, R 18 W/E  
4620 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5004  
Operator: Vincent Oil Corporation  
Name & Address 100 N. Main, Ste. 500  
Wichita, KS 67202

Lease Name Vieux Well # 1  
County Kiowa  
Well Total Depth 5050 1164.12 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 15 Month: 9 Year: 19 93

Plugging proposal received from Jeff Sletto  
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5025' w/250 sx & 50 sx at 3670-71', PBD 3650', CIBP at 3650', Perfs at 3616-22'  
1st plug sand back to 3560' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by \_\_\_\_\_ Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 15 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3560' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel; 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1993  
917-93  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 9-23-93  
INV. NO. 38772

Signed Stephen J. Deifer  
(TECHNICIAN)