

To: 1 051825 23  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,006-0000 1  
NE SE, SEC. 22, T 29 S, R 18 W&E  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5004  
Operator: Vincent Oil Corporation  
Name:  
Address 100 N. Main, Ste. 500  
Wichita, KS 67202

Lease Name Unruh Well # 2  
County Kiowa  
Well Total Depth 4942 160.62 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 524

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 12:30 p.m. Day: 3 Months: 8 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

logs: 4 1/2" at 4939' w/225 sx cement, PBTD 3580', Perfs at 3487-90', Port Collar at 3562' w/  
100 sx cement

1st plug sand back to 3440' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 3 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 3440' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pumped 150 sx cement. Maximum pressure 1100 psi and shut in 850 psi.

RECEIVED

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing. KANSAS CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 8-26-94

NO. 41042

Signed Richard W. [Signature] CONSERVATION DIVISION  
(TECHNICIAN) WICHITA, KS