

To: 1 031424
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-21,284-0000
235' E of
C NE SW, SEC. 22, T 29 S, R 18 W/E
1980 feet from S section line
3065 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4243
Operator: Cross Bar Petroleum, Inc.
Name & Address: 151 N. Main, Ste. 630
Wichita, KS 67202-1407

Lease Name Schmidt E Well # 1-22
County Kiowa 161.49
Well Total Depth 4969 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2:55 p.m. Day: 15 Month: 11 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4969' w/300 sx cement, PBD 4897', Perfs at 4288-91, 4881-88, 3492-97'
1st plug sand back to 4238' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150 sx cement.

11-20-1996

RECEIVED
KANSAS
CORPORATION
NOV 21 1996

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:55 p.m. Day: 15 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4238' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2060' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (stamped)
Observe this plugging.

DATE NOV 21 1996

Signed Steve Durant (TECHNICIAN)

FILE NO. 47012