

1091063

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-20,966-0001
C N/2 NW SE SEC. 22, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME UNRUH WELL # 1-22

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 160,91

OPERATOR LICENSE # 3842 7/12 WELL TOTAL DEPTH 4951 FEET

OPERATOR: LARSON OPERATING CO. PRODUCTION CSG: SIZE 5 1/2" @ 4944' WITH 250 SX

NAME AND 562 WEST HIGHWAY 4 SURFACE CASING: SIZE 8 5/8" @ 515' WITH 400 SX

ADDRESS OLMITZ, KS 67564-8561

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 12 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: SQUEEZED PERFS. @ 4261-66, 4290-95, 4314-18, 4727-32

SET CIBP @ 4700' AND 2 SX CEMENT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1250' WITH 11 SX GEL - 50 SX CEMENT. 2ND PLUG AT 545' WITH 50 SX

CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 12 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SET CIBP @ 4700' AND 2 SX CEMENT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE

PULLING. 1ST PLUG AT 1250' WITH 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 545' WITH 50 SX

CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED CEMENTING RECOVERED 2349' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED [Signature] (TECHNICIAN)

DATE 7/18/00

FORM CP-2/3

WV. NO. 1060088

CONSERVATION DIVISION
Wichita, Kansas

JUL 14 2000

STATE CORPORATION COMMISSION

[Signature]