

1 030963

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Operator: K & E Drilling, Inc.
Name &
Address 100 South Main, Suite 300
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling, Inc. RECEIVED
Address Box 347, Chase, KS 67524 STATE CORPORATION COMMISSION
License Number 6050

Company to plug at: Hour: 11 a.m. Day: 28 Month: 7 Year: 19 88Plugging proposal received from Clay Duntz(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457were: 5½" at 4955' PBTD 4800' Perfs at 3477-82'1st plug pump 2 sx hulls and 20 sx cement,2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 12 p.m. Day: 28 Month: 7 Year: 19 88ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement, stopped at 3100',2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"wiper plug and pumped 130 sx cement.Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2800' of 5½" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-4-88INV. NO. 21751

7-28-88
API NUMBER 15- 097-21,028-0001
SW NW, SEC. 23, T. 29 S, R. 18 W/E
3300 feet from S section line
4620 feet from E section line
Lease Name Schmidt "A" Well # 1-23
County Kiowa 161.20
Well Total Depth 4960 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 520

RECEIVED
AUG 1 1988
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed

Steve Luthi
(TECHNICIAN)