

To: 1 031423
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-21,374-0000
70' West of
E/2 SE SW, SEC. 23, T 29 S, R 18 W/4
660 feet from S section line
3040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4243
Operator: Cross Bar Petroleum, Inc.
Name:
Address 151 N. Main, Ste. 630
Wichita, KS 67202-1407

Lease Name Schmidt Trust Well # 1-23
County Kiowa 160.87
Well Total Depth 4950 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 531

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D. S. & W. Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 15 Month: 11 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D.S.&W. Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 4946' w/160 sx cement, PBSD 4889', Perfs at 4872-82'
1st plug sand back to 4822' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:05 p.m. Day: 15 Month: 11 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4822' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 600 psi and shut in 200 psi. 11-20-1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3315' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE NOV 21 1996

Signed Steve Dumit
(TECHNICIAN)

INV. NO. 47010