

1100061

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,132-0000
C NE NW, SEC. 23, T 29 S, R 18 W/EX
4620 feet from N/S section line
3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267
Operator: K & E Petroleum, Inc.
Name & Address 100 South Main, Suite 300
Wichita, KS 67202

Lease Name Schmidt "A" Well # 2-23
County Kiowa 159.71
(Mississippi)
Well Total Depth 4914 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 517

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 17 Month: May Year: 19 85

Plugging proposal received from Harvey Moore
(company name) Abercrombie (phone) 316-262-1841
Elevation 2184

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1120'
1st plug at 1120' with 50 sx cement

2nd plug at 557' with 60 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement
6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Blyde Wiley
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 am Day: 17 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1120' with 50 sx cement, 2nd plug at 557' with 60 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc
(If additional description is necessary, use BACK of this form. Wichita, Kansas)

MAY 28 1985
5-28-1985
CONSERVATION DIVISION

Signed Blyde Wiley
(TECHNICIAN)

INVOICED

DATE 6-6-85
INV. NO. 8371