

To: 1 051826  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
207 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-3

API NUMBER 15-097-21,015-0000  
C6SW SW, SEC. 23, T 29 S, R 18 W/X  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004  
Operator: Vincent Oil Corporation  
Name:  
Address 100 N. Main, Ste. 500  
Wichita, KS 67202

Lease Name Yohn "B" Well # 1  
County Kiowa  
Well Total Depth 4930 160.23 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 515

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187; Medicine Lodge, KS

Company to plug at: Hour: 10 a.m. Day: 3 Month: 8 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

logs: 4 1/2" at 4926' w/225 sx cement, PSTD 4700', Perfs at 3407-3411'

1st plug pump 1 sx hulls and 20 sx common cement to 3300',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 3 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx common cement to 3300',

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 1000 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.) RECEIVED

INVOICED observe this plugging.

DATE 8-26-94

INV. NO. 41043

Signed Richard M. Lacey (TECHNICIAN) AQS

CONSERVATION  
FORM 101A  
Rev.