

1030259

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,935-0000
C NW SE , SEC. 26 , T 29 S, R18 W/X

1980 FSV feet from ~~XXX~~ SE Corner of section line
1980 FEL feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8819

Lease Name Parkins Well # 1

Operator: Cinco Energy Company

County Kiowa

Name & Address P. O. Box 3723

Well Total Depth 5025 163.31 feet

Victoria, TX 77903-3723

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Service License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 27 Month: August Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" set at 5000' PBD 4979' Perfs at 4441-49'

1st plug sand back to 4315' and dump 5 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and

150 sx cement.

Plugging Proposal Received by Steve Quivont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:25 pm Day: 27 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 5000' PBD 4979' Perfs at 4441-49'

1st plug sanded back to 4315' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150

sx cement.

Bud Metz went to the plugging

Maximum pressure 800 psi and shut in pressure 400 psi

Remarks: Cemented by Halliburton. They recovered 2998' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

observe this plugging.

SEP 04 1984

Signed Steve Quivont
(TECHNICIAN)

INVOICED

DATE 9-10-84

INV. NO. 3597

CONSERVATION DIVISION
Wichita, Kansas