

To: 1051691 7-7  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,478-A  
C NE SE  
SEC. 16 T. 29 S. R. 20 W/E  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 31214  
Operator: Freepoint Pipe & Supply  
Name & Address: P.O. Box 5115  
Edmond, OK 73083-5115

Lease Name McCormick Well # 1  
County Kiowa  
Well Total Depth 5260 170.95 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 560

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address P.O. Box 506, Liberal, KS

Company to plug at: Hour: 1 p.m. Day: 6 Month: 7 Year: 19 93

Plugging proposal received from Kirby Lillard  
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5247' w/150 sx cement, PBD 5258', Perfs at 5121-31'  
1st plug pump 2 sx hulls and 25 sx cement,  
2nd plug at 1250' with 50 sx cement,  
3rd plug at 590' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3 p.m. Day: 7 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 5000',  
Spotted plugs through casing:  
2nd plug at 1250' with 50 sx cement,  
3rd plug at 590' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 9 1993

Remarks: Used common cement by Sargent's. Recovered 3033' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this report.)

INVOICED  
observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

DATE 7-28-93  
INV. NO. 38223

Signed Richard W. Lacy (TECHNICIAN)