

To: 1 090052
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-8
API NUMBER 15- 097-21,301 - 0000 59 R
N of C, SEC. 33, T. 29 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033
Operator: Murfin Drilling Company
Name & Address: 250 N. Water, Suite 300
Wichita, KS 67202

2790 feet from S section line
2640 feet from E section line

Lease Name Brown-Allen Well # 1
County Kiowa 160.55
Well Total Depth 4940 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:05 a.m. Day: 8 Months: 2 Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4882' w/175 sx cement, Open hole 4882-4940'
1st plug sand back to 4830' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 8 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4830' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 100 psi and shut in 0 psi.

FEB 12 1991
2-12-1991
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
OBSERVE THIS PLUGGING.

DATE 2-27-91

Signed _____ (TECHNICIAN)

INV. NO. 30923