

15-097-10162-0000 4-15

240

To: 1 090069
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
202 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-Drill completion date 11/59
C. N/2 NW SE, SEC. 33, T. 29 S, R. 18 W/R
2310 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004
Operator: Vincent Oil Corporation
Name & Address: 100 N. Main, Suite 500
Wichita, KS 67202

Lease Name Brown "C" Well # 1
County Kiowa 161.33
Well Total Depth 4964 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:45 a.m. Day: 15 Month: 4 Year: 1991

Plugging proposal received from Mark Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4967' w/150 sx cement, Perfs at 4900-14', records not available on depth of original squeeze.
1st plug sand back to 4850' and dump 4 sx cement on top of sand through bailer,
2nd plug perforate at 1200' and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN).

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 15 Month: 4 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of sand through bailer,

2nd plug perforated at 1200' and pumped 150 sx cement into perfs-3 barrels per minute, 600# pressure.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-22-91
INV. NO. 31647

RECEIVED APR 17 1991 Signed [Signature] (TECHNICIAN)