

1 030750

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,221-0000  
SW SE, SEC. 33, T 29 S, R 18 W/E  
660 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Brown "B" Well # 1

Operator: Vincent Oil Corporation  
Name & Address 125 North Market, Suite 1110  
Wichita, KS 67202

County Kiowa 163.31

Well Total Depth 5025 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 27 Month: 10 Year: 19 86

Plugging proposal received from Terry McRae

(company name) Murfin Drilling (phone) 913-743-2559

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2169' GL  
Anhydrite 1250'

1st plug at base Anhydrite with 50 sx cement

2nd plug at 30' below surface pipe with 50 sx cement

3rd plug at 40' with 10 sx cement

4th plug to circulate rathole with 15 sx cement, 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2 p.m. Day: 27 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1300' with 50 sx cement

2nd plug at 350' with 50 sx cement

3rd plug at 40-0' with 10 sx cement

4th plug to circulate rathole with 15 sx cement

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1986

Remarks: Used 60/40 Pozmix 2% gel, 3% cc by B.J. Titan. 10-29-1986  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If checked, did not) observe this plugging.

DATE 10-29-86

Signed Steve Luthi  
(TECHNICIAN)

INV. NO. 15252

10-27

Date September 16, 1986  
month day year

API Number 15- 097-21221-0000  
Sec 33... Twp. 29.. S, Rg. 18... East  
660... Ft. from South Line of Section  
2310... Ft. from East Line of Section

OPERATOR: License # 5004  
Name Vincent Oil Corporation  
Address 125 North Market, Suite 1110  
City/State/Zip Wichita, Kansas 67202  
Contact Person Donna Manda  
Phone 316-262-3573

CONTRACTOR: License # 16033  
Name Murfin Drilling  
City/State Wichita, Kansas 67202

Well Drilled For: Well Class: Type Equipment:  
 Oil  SWD  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

If OWWO: old well info as follows:

Operator  
Well Name  
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Seaming will be done immediately upon setting production casing  
Date 9-11-86 Signature of Operator or Agent Richard A. Hiebsch Title Vice President

For KCC Use:

Conductor Pipe Required 275-200 feet; Minimum Surface Pipe Required 275-200 feet per Alt. (1)  
This Authorization Expires 3-12-87 Approved By 9-12-86

More 10-16-86 8 1/2 Q 275'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1200 Base anhr feet depth with 50 sxs of 60/40 poz, 2% gel, 3% cc  
2nd plug @ 600 30' ant. surf feet depth with 50 sxs of !!  
3rd plug @ 40 feet depth with 10 sxs of !!  
4th plug @ feet depth with sxs of  
5th plug @ feet depth with sxs of  
(2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER Jerry McRoy  
TD 5025 FORMATION MISS  
SURFACE PIPE 8 7/8 @ 319  
ANHYDRITE NA ELEVATION 2178/10 2169 G.L.  
STARTING TIME & DATE 11:00 AM 10-27-86  
COMPLETION TIME & DATE 2:00 PM  
1st PLUG @ 1300 FT. W/ 50 SX  
2nd PLUG @ 350 FT. W/ 50 SX  
3rd PLUG @ 40-0 FT. W/ 10 SX  
4th PLUG @ FT. W/ SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ 10 SX  
WATER WELL PLUGGED W/ Hair SX  
CEMENT COMPANY S. T. Titlow  
TECHNICIAN 60/40 2% gel 3% cc

RECEIVED  
STATE CORPORATION  
CONS. DIV. WICHITA  
OCT 29 1986