

1090992

TO: STATE CORPORATION COMMISSION

4-2

API NUMBER 15-097-10,095-0000
NW NE SE SEC. 33, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PARKIN #A-1 WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

OPERATOR LICENSE # 31925

WELL TOTAL DEPTH 4960 161.20 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 5 1/2" @ 4959' WITH 150 SX

NAME AND 249 BETH DRIVE SURFACE CASING: SIZE 8 5/8" @ 401' WITH 225 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 02 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4897-4902

1ST PLUG SANDED TO 4850' WITH 5 SX CEMENT ON TOP.

2ND PLUG SHOOT CASING AT 1150' PUMP 50 SX CEMENT. SHOOT CASING AT 622'.

3RD PLUG PULL TO 430'. PUMP IN 50 SX CEMENT.

4TH PLUG PULL TO 40'. CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 02 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4850' WITH 5 SX CEMENT ON TOP.

2ND PLUG SHOT CASING AT 1150'. PUMP 50 SX CEMENT. SHOT CASING AT 622'.

3RD PLUG PULL TO 430'. PUMP 50 SX CEMENT.

4TH PLUG PULL TO 40'. CIRCULATE CEMENT TO SURFACE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 622' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING. RECEIVED STATE CORPORATION COMMISSION SIGNED

Steve Middleton (TECHNICIAN) FORM CP-2/3

INVOICED

DATE APR 16 1999

APR -7 1999

4-7-1999

INV. NO. 60851

CONSERVATION DIVISION WICHITA, KANSAS