

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21124-00-00
Spot: CE2NENW Sec/Twnshp/Rge: 34-29S-18W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SCHMIDT - G Well Number: 1
County: KIOWA Total Vertical Depth: 4999 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/2 47
Surface Casing: Size 8.625 feet: 477 WITH 150 SX CMT
Production: Size 4.5 feet: 4998 WITH 200 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/17/2002 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4730' & 4 SX CMT. 1ST PLUG AT 1200' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/17/2002 5:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4900'. PERFS AT 4782-87'. SAND TO 4730' WITH 4 SX CMT ON TOP. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 1200'. 2ND PLUG PULL TO 500' AND PUMP 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD CIRCULATION THOUGHOUT JOB.

RECEIVED
MAY 22 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BYACID SERVICES. RECOVERED 3240' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed 
(TECHNICIAN)

INVOICED

DATE 5-23-02

ATTN: 2002061830

MAY 20 2002

Form 117-23

MP