


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 13 Twp. 29 Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner White & Shield Oil & Gas Corporation
Lease Name Larkin Well No. 1
Office Address Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/17/66 19
Plugging completed 12/23/66 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation Depth to top Bottom Total Depth of Well 5242 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	661	none
				5 1/2	5237	2894'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked bottom, ran sand to 5175'. Dumped 5 sacks cement, top of cement was 5123'. Cleaned out cellar, rigged up on 5 1/2, had 34" tension, loaded hole. Shot pipe at 5015, 4910, 4890, 4881, 4874, 4561, 4453, worked pipe. No gain in tension. Shot pipe @ 4361, 4276, 4166, 4046, 3928, 3818, 3709, 3618. Mud came in, got down to 3303'. Shot pipe, worked pipe, no gain in tension. Shot pipe at 3110, lost 4" tension. Lost wire line in hole. Fished wire line out, mud came in, got down to 2900'. Shot pipe at 2888, worked pipe loose, pulled 30 joints. Pulled 63 joints of 5 1/2. Cleared floor, loaded junk rack, tried to bail hole down, could not. Set 10' rock bridge at E 669. Dumped 15 sacks cement with 3" dump bailer. Rack unit, tallied. Dug out braden head, cleaned braden head. Left surface pipe open to 614' for farmers water well.

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1967
1-9-67

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 29 day of Dec, 1966
My commission expires Oct 22, 1970
Notary Public.

