

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20680-00-01.

LEASE NAME Heinze "A" OWWO

WELL NUMBER 1

3300 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 14 TWP. 29S RGE. 19 ~~XXXXXX~~ (W)

COUNTY Kiowa

Date Well Completed 8-9-00

Plugging Commenced 8-6-01

Plugging Completed 8-6-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market, Suite 1075, Wichita, KS 67202

PHONE#(316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-5-01 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Stotler Depth to Top 3571 Bottom 3580 T.O. 3765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	681	0
				4 1/2	3658	2409

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set:

Set CIBP at 3520 ft. Shot casing at 2550 ft. Loaded hole with 16 sxs gel, 40 bbls  
Spotted 20 sxs at 1380 ft. 50 sxs at 100 ft. and 10 sxs at 40 ft. Total recovery was  
2409 ft. of 4 1/2 casing.

Name of Plugging Contractor Plains, Inc. License No. 4072

Address P. O. Box 346, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Richard A. Hiebsch (Operator) o  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts  
statements, and matters herein contained and the log of the above-described well as filed and  
the same are true and correct, so help me God.


(Signature) Richard A. Hiebsch

(Address) 125 N. Market, Suite 1075, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of August, 2001

Yolanda Eubanks  
Notary Public

My Commission Expires:



RECEIVED  
Form CP-4  
05-88

AUG 28 2001  
8-28-01  
KCC WICHITA *of*