


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Flat

Kiowa County, Sec. 10 Twp. 29S Rge. 19 (W)  
Location as "NE/CNW/SW" or footage from lines NE SE  
Lease Owner Carter & Mandel Company  
Lease Name Kelley Well No. 1  
Office Address Lubbock, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-3 19 65  
Application for plugging filed 11-9 19 65  
Application for plugging approved 11-3 19 65  
Plugging commenced 11-3 19 65  
Plugging completed 11-3 19 65  
Reason for abandonment of well or producing formation Dry Hole 65

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 5055 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	661	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300'  
Set first plug at 300' with 1/4  
sack hulls, 25 sacks cement  
Filled with heavy mud to 40'  
Set second plug at 40' with 1/4  
sack hulls and 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1965

11-23-65  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of November, 19 65

My commission expires May 1, 1966

Donna F. Miller  
Notary Public.

WELL LOG

COMPANY: Carter & Mandel Company  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Kelley #1  
 LOCATION: NE SE Section 10-29S-19W  
 Kiowa County, Kansas  
 COMMENCED: October 22, 1965  
 COMPLETED: November 3, 1965  
 ELEVATION: E.L. 2342

0 - 240	Surface clay and sand	
240 - 661	Shale	Set 8-5/8" casing at 661 with 400 sacks cement
661 - 1340	Redbed and shale	
1340 - 2355	Shale and Shells	
2355 - 4630	Lime and Shale	
4630 - 4720	Lime	
4720 - 4840	Lime and Shale	
4840 - 4910	Lime	
4910 - 5055	Lime and shale	
5055	T. D.	

LOG TOPS: *Douglas 4308*  
*Kansas Housing 4402*  
*mermentau 4870*  
*Base of mermentau 5010*  
*Top of Mississippi 5042*

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-15-65  
 NOV 15 1965

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Kelley #1 located NE SE Section 10-29S-19W, Kiowa County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 9th day of November, 1965.

*Donna F. Miller*  
 Donna F. Miller, Notary Public

My commission expires May 1, 1966