

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Grant

County. Sec. 14 Twp. 29 Rge. 35 (E) (W)

Location as "NE/CNW/SW" or footage from lines C/NW/SE

Lease Owner Ashland Oil & Refining Company

Lease Name E. H. Miller Well No. 1

Office Address P.O. Box 127 - Satanta, Kansas 67870

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 16, 19 62

Application for plugging filed March 26, 19 68

Application for plugging approved March 27, 19 68


Plugging commenced April 5, (10:30 a.m.) 19 68

Plugging completed April 5, (11:30 a.m.) 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well E. J. Eves, Sublette, Kansas

Producing formation Council Grove Depth to top 3041 Bottom 3051 Total Depth of Well 3164 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Panoma Council Grove	Gas	3041	3051	2 7/8	3164	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

7" to 715' Circulated w/cement
2 7/8" to 3164' Circulated w/cement

Top perforations 2921'

Plug well w/100 sacks cement top to bottom

Halliburton Pump Truck - No Pipe Pulled

Plug Back TD 3106'

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

4-11-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Cementing Company

Address P.O. Box 129 - Liberal, Kansas

STATE OF Kansas, COUNTY OF Haskell, ss.

Felix C. Turley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Felix C. Turley

P.O. Box 127 - Satanta, Kansas 67870

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 68

My commission expires October 1, 1970

H. J. Tinsley Notary Public.

15-067-10036-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company-UNITED PRODUCING, INC.
Farm- E. H. Miller No. 1

SEC. 14 T. 29 R35W
6 NW SE

Well No. 3106
Drilled 9-5-62 Comp. 9-20-62
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 6-5-65

County Grant
KANSAS



Elevation. 3058' UGB

Production. TEMPORARILY ABANDONED

CASING:
7" 715' 300 sx.
2 7/8" 3104' 550 sx.

Figures indicate Bottom of Formations:

Complete Louisiana Log Not Available

~~NO DRILLERS LOG AVAILABLE:~~

Ran Radio Active Logs. Perforated Council Grove 3041-46' & 3050-51' w/ 1 shot per foot. Swabbed hole down. Preparing to acidize.
PBTB 2995'. Acidized Council Grove perforations 3041-46' & 3050-51' w/ 1,000 gal 15% acid. Swabbed load, no shows.
Set plug at 2995'. Perforated Council Grove 2921' & 2924-34' w/ 1 jet per foot. Acidized w/ 1,000 gals 15% acid. Swabbed load, 8bbs formation water, very slight show of gas. (Chl. 106,000 ppm). Well temporarily abandoned 9-16-62. FINAL REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1968
CONSERVATION DIVISION
Wichita, Kansas

3-28-68

Tops: Scout	
Red bed	668
Winfield	2645
Council Grove	2888
TD	3106