

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-067-00082-0000

LEASE NAME LAHEY, T.J.

WELL NUMBER 1

2540' Ft. from N Section Line

2540' Ft. from E Section Line

SEC. 28 TWP. 29 RGE. 35 (E) or (W)

COUNTY GRANT

Date Well Completed 3-12-45

Plugging Commenced 9-30-96

Plugging Completed 10-03-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR MESA OPERATING CO.

ADDRESS 5205 N. O'CONNOR SUITE 1400 IRVING, TX 75039

PHONE (972) 444-9001 OPERATORS LICENSE NO. 04824

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-25-96 (date)

by STEVE DURRANT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? ON FILE

Producing Formation CHASE Depth to Top 2450' Bottom 2664' T.D. 2695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From 3'	To 680'	Size 10 3/4"	Put in 680'	Pulled out 3'
Top of sand fill	1089'	1065'	2503'	7"	2503'	1065'
CHASE	2450'-2664'	2473'	2695'	5 1/2"	222'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Shot 7" csg. in collar @ 1065', csg. free. Set 100 SX cmt. plug thru 7" csg. @ 915'-1065'. Set 90 SX cmt. plug @ 575'-725'. Set 50 SX cmt. plug @ 250'-300'. Set 20 SX surface cmt plug @ 3'-35' BGL. All cmt plugs displaced with 9.0 ppg 36 nismuc pumped 20 sx cmt thru 1" down 10 3/4" annulus cut off 10 3/4" csg 3' BGL. Welded on plate.

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC.

License No. RECEIVED  
KANSAS CORPORATION COMMISSION

Address RT. Box 49 BA TYRONE, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MESA OPERATING CO.

OCT 08 1996

STATE OF TEXAS COUNTY OF DALLAS, ss.

10-8-96  
CONSERVATION DIVISION  
WICHITA, KS


TROY A. HOEFER

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Troy A. Hoefer

(Address) 5205 O'CONNOR STE. 1400, Irving, TX 75039



SWORN TO before me this

7th day of OCTOBER, 19 96

Notary Public

My Commission Expires: 9-10-97  
USE ONLY ONE SIDE OF EACH FORM