

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-215280000

LEASE NAME HJV WILLIAMS "A"

WELL NUMBER 1

2000 Ft. from N Section Line

1850 Ft. from E Section Line

SEC. 31 TWP. 29S RGE 35 (E) or (W)

COUNTY GRANT

Date Well Completed 03-22-2003

Plugging Commenced 03-22-2003

Plugging Completed 03-23-2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S. TAYLOR ST., SUITE 400, AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 03-21-2003 (date)

by MR. STEVE DURANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? NO

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 5700'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION
4-7-03
APR 07 2003
CONSERVATION DIVISION
WICHITA, KS

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1705	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. TIH W/4-1/2" DP TO 2934'. SPOT 100 SXS 60/40 POZ W/6%GEL @ 2934. TOH TO 1720' & SPOT 50 SXS. TOH TO 600' & SPOT 40 SXS. TOH TO 40' & SPOT 10 SXS AT 0-40'. SPOT 15 SXS IN RH & 10 SXS IN MH. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287-99997

Address P. O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey

L. MARC HARVEY, ENGINEERING TECHNICIAN III

(Address) 701 S. TAYLOR, SUITE 400, AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 3 day of April, 2003

Lori Pearson
Notary Public



My Commission Expires: 2/26/05