

LEASE NAME MLP Nicewander A

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

1930 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 29 RGE. 35 or (W)

COUNTY Grant

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N Kansas PO Box 2528 Liberal, ks. 67905

PHONE (620) 629 4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

Date Well Completed 8-16-94

Plugging Commenced 5-8-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-8-01

The plugging proposal was approved on 5-7-01 (date)

by Kevin Strube (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5458 Bottom 5668 T.D. 5806

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1805	-
				5 1/2	5798	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each so Mixed 2 sx hulls to 25 sx cmt. to plug perfs from 5458 to 5258 - followed w/mud to 1830 - mixed 25 sx 1830 to 1630 - mud to 800 - mixed 90 sx from 800 to 0. Mixed 10 sx down 8 5/8 - 5 1/2 annulus to pres up to 500 PSI. Cut off 8 5/8 to 5 1/2 to capped 8 5/8 3-ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515



NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

JUN 7 2001  
 6-7-01

Kenny Andrews (Employee of Operator) or (Operator),  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
 statements, and matters herein contained and the log of the above-described well as filed to  
 the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, ks. 67905

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of June, 2001

Anita Peterson  
 Notary Public

My Commission Expires: Oct 1, 2001



OR  
 Form CP-  
 Revised 05-01